

A Constructability WA case study: One of many successfully completed projects over our 35 year history in the Civil Construction Industry.

T155 - IRON ORE CAR DUMPER -PORT HEADLAND

CACK CYCO)

CLIENT

FMG EPCM - Worley Parsons

COMMENCEMENT

May 2011

COMPLETION

June 2012

PROJECT VALUE

56.0 Million

Scope of Works/ Contract Objective

- > The scope of works entailed construction of the T155 Car Dumper- vault level, apron feeder level, trunion level, rail drive level, ingo and outgo foundations and double conveyor tunnels
- > The contract objective was to construct within budget and ahead of the approved baseline programme

Construction Quantities

- > 720 c/m- construction of blinding installed
- > 18718 sq./m structural formwork installed including false work and supports
- > 2665 tonnes reinforced steel installed
- > 15,402 cu/m structural concrete poured

Safety Performance

- > 25-40 personnel onsite during the project - 215,300 man hours
- > 1 lost time injury
- > 1 medically treated injury
- Lost time injury frequency rate: 9.29

Environmental Performance

- No environmental incidents reported
- > 10 Audits completed to 100% compliance

Project Challenges

- Short duration for mobilisation to Site - 3 weeks
- Craneage and Logistics flexibility of sequence and program of works to align with client requirements
- Wet season disruption to works progress on three separate occasions
- Weather affected construction program impacting on-site with a greater interface with other contractors

Project Achievements

- Contracted works completed
 4 weeks ahead of schedule
- Contracted works completed within the allocated budget